1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

SPONSOR: Primacoustic, a Division of Radial Engineering Ltd.

Port Coquitlam, BC, Canada

Sound Absorption RALTM-A23-086

CONDUCTED: 2023-04-10

Page 1 of 9

ON: ECOScapes Slat Wall (MDF with wood veneers face and PET backing) TELAFILL - PET

Panels in cavities

TEST METHODOLOGY

Riverbank Acoustical LaboratoriesTM is accredited by the U.S. Department of Commerce, National Institute of Standards and Technology (NIST) under the National Voluntary Laboratory Accreditation Program (NVLAP) as an ISO 17025:2017 Laboratory (NVLAP Lab Code: 100227-0) and for this test procedure. The test reported in this document conformed explicitly with ASTM C423-22: "Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method." The specimen mounting was performed according to ASTM E795-23: "Standard Practices for Mounting Test Specimens During Sound Absorption Tests." A description of the measurement procedure and room specifications are available upon request. The results presented in this report apply to the sample as received from the test sponsor.

INFORMATION PROVIDED BY SPONSOR

The test specimen was designated by the sponsor as ECOScapes Slat Wall (MDF with wood veneers face and PET backing) TELAFILL - PET Panels in cavities. The following nominal product information was provided by the sponsor prior to testing. The accuracy of such sponsor-provided information can affect the validity of the test results.

Product Under Test

Product Names: ECOScapes Slat Wall

TELAFILL PET Panels

Manufacturer: Primacoustic, a Division of Radial Engineering Ltd.

SPECIMEN MEASUREMENTS & TEST CONDITIONS

Through a full external visual inspection performed on the test specimen, Riverbank personnel verified the following information:

Base Layer (TELAFILL)

Material: PET felt Panels
Thickness: 25.11 mm (0.9885 in.)
Overall Weight: 15.42 kg (34 lbs)



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE

SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

Primacoustic, a Division of Radial Engineering Ltd. 2023-04-10

RALTM-A23-086

Page 2 of 9

Face Layer (ECOScapes)

Materials: Panels comprised of wood slats over PET felt Dimensions: 1 panel @ 305 mm (12 in.) by 2438 mm (96 in.)

3 panels @ 806 mm (31.75 in.) by 2438 mm (96 in.) 1 panel @ 38 mm (1.5 in.) by 2438 mm (96 in.)

Thickness: PET felt @ 9.21 mm (0.3625 in.)

Wood slats @ 12.76 mm (0.5025 in.)

Total @ 21.01 mm (0.827 in.)

Overall Weight: 61.23 kg (135 lbs)

Overall Specimen Properties

Size: 2.74 m (108.0 in) wide by 2.44 m (96.0 in) long

Thickness: 0.02 m (0.951 in) Weight: 76.66 kg (169.0 lbs)

Mass per Unit Area: 11.46 kg/m² (2.35 lbs/ft²)

Calculation Area: 6.689 m² (72. ft²)

Test Environment

Room Volume: 291.98 m³

Temperature: $20.2 \,^{\circ}\text{C} \pm 0.2 \,^{\circ}\text{C}$ (Requirement: $\geq 10 \,^{\circ}\text{C}$ and $\leq 5 \,^{\circ}\text{C}$ change) Relative Humidity: $61.05 \,^{\circ}\text{M} \pm 1.9 \,^{\circ}\text{M}$ (Requirement: $\geq 40 \,^{\circ}\text{M}$ and $\leq 5 \,^{\circ}\text{M}$ change)

Barometric Pressure: 99.9 kPa (Requirement not defined)

MOUNTING METHOD

Type C-25 Mounting: Test specimen was mounted on 25 mm (1 in.) thick wood furring strips spaced 610 mm (24 in.) on centers and laid directly against the test surface. This produced a 25 mm (1 in.) thick cavity enclosed with wood furring behind the ECOScapes panels. The cavity was filled with TELAFILL PET felt panels that had a 25.11 mm (0.9885 in.) uncompressed thickness. Perimeter edges were sealed with metal framing and tape.



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-A23-086 Page 3 of 9

Primacoustic, a Division of Radial Engineering Ltd. 2023-04-10



Figure 1 – Specimen mounted in test chamber



Figure 2 – TELAFILL panels installed in cavities between wood furring strips



RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-A23-086 Page 4 of 9

Primacoustic, a Division of Radial Engineering Ltd. 2023-04-10



Figure 3 – ECOScapes panels partially installed over wood furring and TELAFILL panels



Figure 4 – Detail of specimen materials



RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

Primacoustic, a Division of Radial Engineering Ltd. 2023-04-10

RALTM-A23-086
Page 5 of 9

TEST RESULTS

Specimen total absorption and absorption coefficient are tabulated at the eighteen standard frequencies. A graphic presentation of the data and additional information appear on the following pages.

1/3 Octave Center			
Frequency	Total Absorption	Total Absorption	Absorption
(Hz)	(m^2)	(Sabins)	Coefficient
100	1.26	13.53	0.19
** 125	1.93	20.79	0.29
160	2.27	24.49	0.34
200	2.76	29.74	0.41
** 250	3.70	39.78	0.55
315	5.05	54.32	0.75
400	5.89	63.39	0.88
** 500	6.54	70.44	0.98
630	6.99	75.28	1.05
800	7.33	78.88	1.10
** 1000	7.12	76.67	1.06
1250	6.78	73.01	1.01
1600	6.45	69.41	0.96
** 2000	6.13	65.94	0.92
2500	5.84	62.81	0.87
3150	5.69	61.23	0.85
** 4000	5.92	63.71	0.88
5000	5.80	62.40	0.87

SAA = 0.88NRC = 0.90



1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

Primacoustic, a Division of Radial Engineering Ltd. 2023-04-10

RALTM-A23-086 Page 6 of 9

TEST RESULTS (continued)

The sound absorption average (SAA) is defined in ASTM C423-17 Section 3.1.1 as the arithmetic average of the sound absorption coefficients of a material for the twelve one-third octave bands from 200 Hz through 2500 Hz, inclusive, rounded to the nearest integer multiple of 0.01.

The noise reduction coefficient (NRC) is defined from previous versions of ASTM C423 as the arithmetic average of the sound absorption coefficients at 250 Hz, 500 Hz, 1000 Hz, and 2000 Hz, rounded to the nearest integer multiple of 0.05.

Tested by___

Marc Sciaky

Senior Experimentalist

Report by

Keith Kimberling

Test Engineer

Approved by

Eric P. Wolfram

Laboratory Manager

Digitally signed by Eric P Wolfram Date: 2023.04.21

09:08:34 -05'00'

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

Test Report

www.riverbankacoustics.com


FOUNDED 1918 BY WALLACE CLEMENT SABINE

Primacoustic, a Division of Radial Engineering Ltd. 2023-04-10

RALTM-A23-086 Page 7 of 9

SOUND ABSORPTION REPORT

ECOScapes Slat Wall (MDF with wood veneers face and PET backing) TELAFILL - PET Panels in cavities



SAA = 0.88

NRC = 0.90



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NYLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

Primacoustic, a Division of Radial Engineering Ltd. 2023-04-10

RALTM-A23-086

Page 8 of 9

APPENDIX A: Extended Frequency Range Data

Specimen: ECOScapes Slat Wall (MDF with wood veneers face and PET backing) TELAFILL - PET Panels in cavities (See Full Report)

The following non-accredited data were obtained in accordance with ASTM C423-22, but extend beyond the defined frequency range of 100Hz to 5,000Hz. These unofficial results are representative of the RAL test environment only and intended for research & comparison purposes.

1/3 Octave Band Center Frequency (Hz)	Total Absorption (Sabins)	Absorption Coefficient
31.5	-1.15	-0.02
40	-4.92	-0.07
50	-5.08	-0.07
63	4.57	0.06
80	4.03	0.06
100	13.53	0.19
125	20.79	0.29
160	24.49	0.34
200	29.74	0.41
250	39.78	0.55
315	54.32	0.75
400	63.39	0.88
500	70.44	0.98
630	75.28	1.05
800	78.88	1.10
1000	76.67	1.06
1250	73.01	1.01
1600	69.41	0.96
2000	65.94	0.92
2500	62.81	0.87
3150	61.23	0.85
4000	63.71	0.88
5000	62.40	0.87
6300	55.50	0.77
8000	48.64	0.68
10000	45.51	0.63
12500	40.56	0.56



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

Primacoustic, a Division of Radial Engineering Ltd. 2023-04-10

RALTM-A23-086

Page 9 of 9

APPENDIX B: Instruments of Traceability

Specimen: ECOScapes Slat Wall (MDF with wood veneers face and PET backing) TELAFILL - PET Panels in cavities (See Full Report)

		Serial	Date of	Calibration
Description	Model	Number	Certification	<u>Due</u>
System 1	Type 3160-A-042	3160- 106968	2022-07-12	2023-07-12
Bruel & Kjaer Mic And Preamp D	Type 4943-B-001	2311440	2022-09-28	2023-09-28
Bruel & Kjaer Pistonphone	Type 4228	2781248	2022-07-22	2023-07-22
EXTECH Hygro 639	SD700	A.103639	2022-12-07	2023-12-07

APPENDIX C: Revisions to Original Test Report


Specimen: ECOScapes Slat Wall (MDF with wood veneers face and PET backing) TELAFILL - PET Panels in cavities (See Full Report)

Date	Revision	
2023-04-18	Original report issued	


END




Mounting Types Explained




A Mount
Panel is mounted directly to wall.



C25 Mount
Panel is mounted on 1" thick
furring strips, spaced 24" apart.
Cavities are filled with strips of
1" thick Telafill.



C50 Mount
Panel is mounted on 2" thick
furring strips, spaced 24" apart.
Cavities are filled with strips of
2" thick Broadway Glass Wool.



D20 Mount
Panel is mounted on 3/4" thick
furring strips, spaced 12" apart.
Cavities are left empty.